

ASSAM SCIENCE TECHNOLOGY AND ENVIRONMENT COUNCIL
BIGYAN BHAWAN, G.S. ROAD, GUWAHATI-781005

Name of the work: Pathway Development in Assam Bio-Resource Centre
Work site: Madan Kamdev near Baihata Chariali, Kamrup, Assam

TENDER PAPER

Item No.1. S.O.R. No.2.3(I) (A)

Clearing and gridding of road Land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees grith uo to 300mm, removal of stumps of trees cut earier and disposal of unserviceable materials and stacking of serviceable materials including removal and disposal of top organic soil not exceeding 150mm thickness.

Approximate Quantity = 0.32 Hectar

Rate quoted (in % = per ha.

Item No. 2. S.O.R. No.4.9 A(II) (a) Water Bound Macadam

Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding material to fillup the iterstices of coarse aggregate, watering and compacting to the required density.

Approximate quantity = 291.84 cu.m.

Rate quoted (in %) = per cu.m.

Item No.3. S.O.R. (Rural) No. 14.1.

Providing and laying boulder apron for bed protection with stone boulder of minimum size and weight as per Table 1300.1. no fragment weighing less than 25 kg. laid dry complete as per technical specifications clause 13001.

Approximate quantity = 3.60 cu.m.

Rate quoted (in %) = per cu.m.

Item No.4. S.O.R.4.1.1.(a)

Providing brick soling in foundation and under floor with best quality picked jhama brick, sand packed and laid to level and in panel after preparing sub-grade as directed including all labour and materials and if necessary dewatering complete.

Approximate quantity = 29.06 sq.m.

Rate quoted (in %) = per sq.m.

Item No.5. S.O.R. 12.6(C)

Brick masonry work in cement mortar 1:4 in foundation complete excluding pointing and plastering, as per technical specifications.

Approximate quantity = 33.07 cu.m.

Rate quoted (in %)= per cu.m.

Item No.6. S.O.R.2.1.1.(a)

Plain cement concrete works with coarse aggregate of size 13mm to 32mm in foundation bed as directed and specified including dewatering if necessary, and curing complete.

Approximate quantity = 6.79 cu.m.

Rate quoted (in %)= per cu.m

Item No.7. S.O.R.2.2.1.

Providing and laying reinforced cement concrete works in proportion 1:2:4 including dewatering if necessary, and curing complete.

Approximate quantity = 1.38 cu.m.

Rate quoted (in %)= per cu.m

Item No.8. S.O.R.18.1.1(b)i

Supplying, fitting and fixing in position reinforcement bars conforming to relevant I.S. Code for R.C.C. work including straightening, cleaning, cutting and bending to proper shapes and length as per details, supplying and binding with 20G annealed black wire and placing in position with proper blocks, supports, chairs, spacers etc. complete. 8 Tor

Approximate quantity = 2.20 Qtl.

Rate quoted (in %)= per Qtl.

Item No.9. S.O.R. 3.1.5

Providing form work of ordinary timber planking so as to give rough finish including centering, shuttering and propping etc. and removal of the same for in-situ reinforced concrete work.

Approximate quantity = 63.37 sq.m.

Rate quoted (in %)= per sq.m.

Rate Quoted by

Contractor's signature with seal